Service interval display reset on completion of service without VAS 5051B2009/10/30 12:32:14


Service interval display reset on completion of service without -VAS 5051B-

- The corresponding service message must be reset on completion of service.
- The service interval display can be reset with the vehicle diagnostic, testing and information system -VAS 5051B- using the "Adaption" function → Chapter.
- The service interval display can also be reset by implementing the following procedure:

Sequence of operations

- Switch off ignition.
- Press and hold the trip recorder reset button -2- in the dash panel insert.
- Switch on the ignition whilst pressing the button.
- Release the button.

Up to Model Year 1997, the trip recorder displays "Oil change" and as of Model Year 1998 "Oil change service".



 Keep pulling the time setting knob -1- in the dash panel insert until the display is reset.

The display -3- indicates "- - -".

 The next service is accessed by pressing the trip recorder reset button -2- again.

Up to Model Year 1997, the display -3- indicates "In1" and as of Model Year 1998 "Inspection service".

 Keep pulling the time setting knob -1- in the dash panel insert until the display is reset.

The display -3- indicates "- - -".

Up to Model Year 1997:

 The next service is accessed by pressing the trip recorder reset button -2- again.

The display -3- indicates "In2".

 Keep pulling the time setting knob -1- in the dash panel insert until the display is reset.

The display -3- indicates "- - -".

All models:

Switch off ignition.

